

INSPECTION & TEST PLAN (ITP)

Activity: Reinforced Concrete Works — Foundations & Superstructure

Project: Al-Noor Hospital Expansion | ITP Ref: AHX-ITP-CONC-001 Rev 1 | Date: Feb 2024

CODE	MEANING
H	HOLD POINT — work SHALL NOT proceed without witnessed sign-off
W	WITNESS POINT — notified in advance; work may proceed if inspector absent after agreed notice period
R	REVIEW — document review; no physical witness required
M	MONITOR — Contractor self-checks; records available for Engineer audit

No.	Activity / Inspection Point	Reference Document	Acceptance Criteria	Frequency	CTR Code	Contractor	Engineer	Employer
1	Mix design approval — review submitted design for concrete mix	Spec 03.02.1 Concrete Mix	Meet all requirements in Spec Table 1.1	Before 1st pour	R	S	A	—
2	Cement mill certificates — review against Spec 03.02.2	Spec 03.02.2	Conformance to BS EN 197-1	Each delivery lot	R	S	R	—
3	Aggregate grading tests — review lab reports	BS EN 12620	Zone M grading; no deleterious content	Weekly, or per 500m³	R	S	R	—
4	Formwork inspection — verticality, level, strength	Spec 03.03.1 Release agent Drawings	Tolerances per BS EN 13670	Pre-pour, each element	W	S	W	—
5	Rebar inspection — size, spacing, cover	Drawings, BS 8419 Spec 03.20	Per approved drawings ± specified tolerances	Pre-pour, each element	W	S	H	—
6	Pre-pour inspection — cleanliness, serviceability, DPs	Spec 03.03.1, DPs	No standing water; all inserts fixed	Pre-pour, each element	W	S	H	W
7	Slump test — per delivery truck on arrival	BS EN 12350-2	160–200mm (pump mix); reject if outside range	Each truck	M	S	W	—
8	Cube sampling — casting, curing, dispatch	BS EN 12390-2	Min. 4 cubes per 50m³; UKAS certified	As required in Spec	S	S	W	—
9	Concrete temperature check — discharge	Spec 03.03.1, BS EN 12350-3	Discharge 5–30degC; in-place max 70degC differential	Each 700degC differential	M	S	M	—
10	Compaction witness — vibrator use, inspection	Spec 03.03.1, Spec 03.03.2	450mm centres max; no over-lapping	During pour	W	S	W	—
11	Curing witness — commencement, duration	Spec 03.03.1, BS EN 12390-3	7 days minimum; continuous	After each pour	W	S	W	—
12	28-day cube test results — review certificates	BS EN 12390-3 BS EN 206 Cl.8	Characteristic strength f _{ck} met	28 days after pour	R	S	H	—
13	Surface finish inspection — honeycombing, laitance	Spec 03.03.1, BS EN 13670	Max 30 l/ha; no honeycombs	After stripping formwork	W	S	W	—
14	As-built survey — dimensional check of structure	Drawings, BS EN 13670	Tolerances: position ±15mm; level ±10mm	After slitting; plumb	M	L/500 S	W	—

CTR Codes: C = Contractor | E = Engineer | ER = Employer's Representative | A = Approve | S = Submit | H = Hold | W = Witness | R = Review | M = Monitor