

BILL OF QUANTITIES

Al-Noor Hospital Expansion | Civil & Structural Works | Contract No. AHX-2024-CS-001

PROJECT	Al-Noor Hospital Expansion	DOCUMENT TYPE	Bill of Quantities
DOCUMENT NO.	PRJ001-BOQ-Civil-Rev3	REVISION	Rev 3
DATE	15-Jan-2024	STATUS	ISSUED FOR CONSTRUCTION

SECTION 2: EARTHWORKS & SUBSTRUCTURE

Item	Description	Unit	Qty	Rate (AED)	Amount (AED)
2.1	Mobilisation & site clearance including removal of existing vegetation, topsoil strip 150mm	m3	650	125.00	85,000.00
2.2	Bulk excavation in any material to reduced level, max depth 3.5m, including disposal	m3	1425	125.00	178,500.00
2.3	Excavation for pile caps and ground beams, depth not exceeding 2.0m	m3	620	68.00	42,160.00
2.4	Working space allowance around pile caps	m2	180	12.00	2,160.00
2.5	Hardcore filling, 150mm thick, compacted in layers, Type 3 material	m3	1,840	28.50	52,440.00
2.6	Blinding concrete Grade C10/20, 75mm thick below pile caps and ground beams	m3	48	310.00	14,880.00
2.6.1	- Ordinary Portland Cement concrete, Grade C10, in firm natural ground (sandy soil)	m3	32	295.00	9,440.00
2.6.2	- Ordinary Portland Cement concrete, Grade C10, in loose ground	m3	16	335.00	5,360.00
2.7	Anti-termite treatment to underside of slab, including chemical bander	m2	1,840	18.00	33,120.00
2.8	Damp proof membrane 1200 gauge polythene, lapped 300mm at joints	m2	1,900	9.50	18,050.00
2.9	Reinforced concrete Grade C30/37 in pile caps, including formwork	m3	285	1,250.00	356,250.00
2.10	Reinforced concrete Grade C30/37 in ground beams, including formwork	m3	112	1,380.00	154,560.00
2.11	High yield deformed steel reinforcement bars BS 4449 Grade B500B in pile caps	tonne	32.5	4,200.00	161,700.00
2.12	High yield deformed steel reinforcement bars BS 4449 Grade B500B in ground beams	tonne	16.8	4,200.00	70,560.00
				SECTION 2 TOTAL	1,169,380.00

SECTION 4: SUPERSTRUCTURE CONCRETE

Item	Description	Unit	Qty	Rate (AED)	Amount (AED)
4.1	Reinforced concrete Grade C35/45 in suspended slabs, including all formwork and props	m3	680	1,450.00	986,000.00
4.1.1	- Ground floor slab 200mm thick	m3	195	1,380.00	269,100.00
4.1.2	- 1st floor slab 200mm thick	m3	175	1,450.00	253,750.00
4.1.3	- 2nd floor slab 200mm thick	m3	175	1,450.00	253,750.00
4.1.4	- Roof slab 250mm thick including upstand walls	m3	135	1,520.00	205,200.00
4.1.8	Cement concrete Grade 1:1.5:3 (1 cement : 1.5 sand : 3 graded aggregate 4.75mm), mix ratio as specified in 04.3.2	m3	25	1,650.00	41,250.00
4.2	Reinforced concrete Grade C35/45 in columns 300x300mm to 600x600mm	m3	124	1,680.00	208,320.00
4.3	Reinforced concrete Grade C35/45 in shear walls 200-250mm thick	m3	89	1,720.00	153,080.00
4.4	Reinforced concrete Grade C35/45 in beams, various sizes	m3	215	1,580.00	339,700.00
4.5	High yield reinforcement Grade B500B in slabs, columns, beams and walls	tonne	185.5	4,200.00	779,100.00

4.6	Mild steel links and stirrups in beams and columns	tonnes	12.8	4,800.00	61,440.00
				SECTION 4 TOTAL	2,825,640.00

SECTION 5: FINISHES

Item	Description	Unit	Qty	Rate (AED)	Amount (AED)
5.1	Ceramic floor tiles 600x600mm, Grade AA, as Spec Section 09.30.2 laid on 50mm screed	m2	5,200	115.00	592,000.00
5.2	Reinforced cement concrete screed 50mm thick to floors	m2	3,200	48.00	153,600.00
5.2.1	- Concrete Ready-Mix Grade C20, 10 nos batching plant delivery including 1 pump	m3	1,600	985.00	1,576,000.00
5.2.2	- Reinforced cement concrete mix ratio 1:2:4 (cement:sand:20mm aggregate) for floor screed laid to fall	m3	1,200	125.00	150,000.00
5.3	2-coat gypsum plaster to internal walls 15mm total thickness	m2	8,600	38.00	326,800.00
5.4	Emulsion paint to plastered walls, 3 coats, as Jotun Majestic Matt or equal approved	m2	8,600	22.00	189,200.00
5.5	Suspended ceiling, Armstrong Optima 600x600mm mineral fibre tiles in exposed grid	m2	2,800	245.00	686,000.00
				SECTION 5 TOTAL	2,152,240.00

SECTION	DESCRIPTION	AMOUNT (AED)
2	Earthworks & Substructure	1,169,380.00
3	Piling Works (carried forward)	2,340,000.00
4	Superstructure Concrete	2,825,640.00
5	Finishes	2,152,240.00
6	Mechanical & Plumbing (carried forward)	3,100,000.00
7	Electrical Works (carried forward)	1,850,000.00
	GRAND TOTAL (excl. VAT)	13,437,260.00
	VAT @ 5%	671,863.00
	GRAND TOTAL (incl. VAT)	14,109,123.00