

PROJECT	Al-Noor Hospital Expansion — Abu Dhabi	DRAWING NO.	S-023
TITLE	FOUNDATION PLAN & PILE LAYOUT	REVISION	Rev C
DISCIPLINE	STRUCTURAL	SCALE	1:100 @ A1 / NTS @ A4
DRAWN BY	J. Patel	CHECKED BY	Dr. M. Ibrahim
DATE	12 March 2024	APPROVED	K. Williams
ENGINEER	Atkins ME — Structural	STATUS	ISSUED FOR CONSTRUCTION

DRAWING DESCRIPTION & NOTES

This drawing shows the foundation plan for the Al-Noor Hospital Expansion project. All pile positions are shown relative to the established grid system. Grid lines run North-South (1, 2, 3... 12) and East-West (A, B, C... H). All dimensions are in millimetres unless otherwise noted. This drawing is to be read in conjunction with drawings S-021 (Pile Schedule), S-022 (Pile Cap Details), S-024 (Ground Beam Layout), and Geotechnical Report Ref GT-2023-044.

GRID COORDINATES & PILE SCHEDULE EXTRACT

Pile Ref	Grid Location	Pile Type	Diameter	Length	Pile Cap Ref	Level (FFL)	Load (kN)
P-001	A-1	Bored Cast-in-situ	600 dia	18,000	PC-01	±0.000	-2,850
P-002	A-2	Bored Cast-in-situ	600 dia	18,000	PC-01	±0.000	-2,850
P-003	A-3	Bored Cast-in-situ	750 dia	22,000	PC-02	±0.000	-4,200
P-004	B-1	Bored Cast-in-situ	600 dia	18,000	PC-03	±0.000	-2,650
P-005	B-3	Bored Cast-in-situ	750 dia	22,000	PC-04	±0.000	-4,200
P-006	C-2	Bored Cast-in-situ	600 dia	18,000	PC-05	±0.000	-3,100
P-007	C-3 (lift core)	Bored Cast-in-situ	900 dia	25,000	PC-06	-0.200	-6,800
P-008	D-1	Bored Cast-in-situ	600 dia	18,000	PC-07	±0.000	-2,850
P-009	D-4	Bored Cast-in-situ	750 dia	20,000	PC-08	±0.000	-3,950
P-010	E-2	Bored Cast-in-situ	600 dia	18,000	PC-09	±0.000	-2,850

GENERAL NOTES

- All piles shall be constructed in accordance with BS EN 1536:2010 (Bored Piles) and project specification Section 03.10.
- Concrete for piles: Grade C35/45, minimum cement content 400 kg/m3, maximum w/c ratio 0.45, sulphate resistant cement (SRPC) where ground conditions require.
- Pile tolerances: Plan position ±75mm from specified position; Verticality ±1 in 75; Cut-off level ±25mm.
- Pile integrity testing: 100% of piles to be tested by Pile Integrity Test (PIT). Load testing: 1% of total pile count or minimum 2 nos. maintained load tests.
- The Contractor shall verify all grid coordinates on site before pile installation. Any discrepancy to be notified to the Engineer immediately.
- Setting out to be from two permanent benchmarks established by licensed surveyor. Coordinates on Abu Dhabi National Grid (ADNG).
- Do not scale from this drawing. Use figured dimensions only.
- This drawing supersedes all previous issues. Rev C: Pile P-007 diameter increased from 750 to 900mm due to revised column load from structural analysis.

REVISION HISTORY

Rev	Date	Description	By	Checked
A	15-Jan-2024	First Issue for Comment	JP	MI
B	05-Feb-2024	Pile positions revised following updated geotech report	JP	MI
C	12-Mar-2024	Pile P-007 dia increased to 900mm; pile cap PC-06 enlarged	JP	KW